No.	Items.		
17.	Mangalore tiled gabled roof building	37′ × 17′	629 Sq. ft.
18.	Do	52′ × 10′	520 ,,
	Total ..		1,149 ,,
19.	Mangalore tiled room on jungle wood rafters verandah ..	40′ × 9′	360 ,,
	Total ..		360 ,,
20.	Mangalore tiled room on bamboos	15½′ × 8¾′	1,35·6 sqr.
21.	Zinc-sheet roofed vernadah	21½′ × 8¾′	188 S.ft.
22.	Do latrine	11′ × 3′	33 ,,
	Total ..		221 ,,
23.	Terraced building	43′ × 18′	774 ,,
24.	Do raised portion	30½′ × 14½′	442 ,,
25.	Stone mantap	30½′ × 8′	244 ,,
	Mangalore tiled gabled roof with flat tiles ceiling	2×5 × 6¾	67·5 ,,
	Wooden gate shutters with stone posts, etc., complete ..	2×6×6¾	81 ,,
	Total ..		148·5 ,,

Narale tree big	1
Do small	1
Cocoanut trees	5
Mulbery tree	1
Seema Hunisey	1
Bairna mara	1
Do small	1

One stone revetted well 6′ diameter and 30′ deep.

B. R. GARUDACHAR,
Executive Engineer.

BANGALORE DIVISION.

Abstract Notification dated 15th October 1938.

The attention of the public is hereby invited to the detailed notification, inviting sealed tenders for restoring the breached tank, called as Subedarkere of Kadu Jekkasandra Village of Kankanhalli Taluk published on pages 1816-1818 of Part VI of the *Mysore Gazette*, dated 20th October 1938.

The last date for the receipt of the tenders is 12 NOON on 11th November 1938. Duplicate challan for having credited the deposit amount of Rs. 450 into the State Huzur Treasury under "17 (*a*) P.W. Deposits" should accompany the tender.

Abstract Notification dated 15th October 1938.

The attention of the public is hereby invited to the detailed notification, inviting sealed tenders for improving the Government Middle School (Boys') at Chennapatna by putting up two additional rooms in the rear side, published on pages 1819-1821 of Part VI of the *Mysore Gazette*, dated 20th October 1938.

The last date for the receipt of the tenders is 2 P.M. on 10th November 1938. Duplicate challan for having credited the deposit amount of Rs. 103 to the State Huzur Treasury under "17 (*a*) Public Works Deposits" should accompany each tender.

Abstract Notification dated 17th October 1938.

The attention of the public is hereby invited to the detailed notification, inviting sealed tenders for constructing two additional rooms to the Government Middle School at Devanhalli, published on pages 1863-1865 of Part VI of the *Mysore Gazette*, dated 20th October 1938.

The last date for the receipt of the tenders is 2 P.M. on 12th November 1938. Duplicate challan for having credited the Deposit amount of Rs. 150 into the State Huzur Treasury under "17 (*a*) P.W. Deposits" must accompany the tender.

Notification dated 30th October 1938.

Sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, upto 2 P.M. on 21st November 1938 for restoring Adrangi Hosakatte or Settarkatte, Reg. No. 140 of Magadi Taluk.

2. Tenders in the prescribed form obtainable from the office of the Executive Engineer, Bangalore Division, should be addressed to the Executive Engineer, Bangalore Division, in a sealed cover and superscribed as "Tender for Restoring Adrangi Hosakatte." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a duplicate Challan for having credited into the treasury the deposit amount of Rs. 825 under "17 (a) P. W. Deposits" or Mysore Government Bonds, duly endorsed at face value or market value, whichever is less, as earnest money. The earnest money of the successful tenderer will be retained as security deposit for due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 22nd November 1938, at 3 P.M. The final acceptance of the tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the Departmental Schedule Contract form after depositing an additional sum of Rs. 825 for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay specifications (1931).

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Bangalore Division, on all working days between 11 A.M. and 5 P.M., and may be obtained from that officer on payment of Rs. 5 for each.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page, noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department Schedule of Rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof, or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer, on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions, or additions at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of May 1941, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 825 per day, which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

Approximate quantities required for restoring Adarangi Hosakatti or Settarkatti, Reg. No. 140 of Magadi Taluk.

Item No.	Description of work	Unit	Rate	Quantity	Rate to be quoted in	
					Words	Figures
			Rs. a. p.			
1	Clearing jungle with roots and cutting grips and steps on the bund, etc.	Grade	3 0 0	12		
2	Earthwork to bund with required lead and lift and consolidation	C.yd.	0 3 6	4,300		
3	Clearing the wet silt in the breached portion by buckets and basins and filling the rear gap of breach beyond the toe of rear slope	C.yd.	0 3 0	9,372		
4	Refilling the above with fresh earth from draft clearing with lead and lift, etc. ..	,,	0 4 6	6,537		
5	Earthwork foundation for puddle trenches ..	,,	0 4 0	2,595		
6	Puddle wall with good clay mixed with gravel	,,	0 12 0	3,027		
7	Earthwork for breach filling as per deduction in earthwork to bund with lead and lift	,,	0 5 0	3,770		
8	Rough stone revetment new with the required lead and lift, including jelly backing and jelly wedging, etc., complete	,,	1 8 0	2,572		
9	Gravel backing to revetment from draft clearing	,,	0 6 0	857		
10	Providing jelly drain along the bund ..	,,	1 8 0	52		
11	Turfing the rear slope and watering till it is satisfactory	S.yd.	0 0 10	5,425		
12	Providing and fixing B. M. stones on bed slabs including cutting figures and painting, etc., complete	No.	2 0 0	2		
13	Providing and fixing Register No. stone on a bed slab including cutting figures and painting etc., complete	,,	3 0 0	1		

Item No.	Description of work	Unit	Rate	Quantity	Rate to be quoted in	
					Words	Figures
			Rs. a. p.			
14	Providing and fixing grade stones on bed slabs, including cutting figures and painting, etc., complete	No	2 0 0	14		
15	Providing and fixing Index stones including painting, etc., complete	,,	0 6 0	14		
16	Providing and fixing gauge stone on a bed slab including cutting figures, masonry work and painting, etc., complete ..	,,	14 0 0	1		
	Constructing a Sluice.					
1	Earthwork cut opening the bund and refilling the same with watering and tamping, etc.	C.yd.	0 5 0	200		
2	Earthwork excavation for foundation and using the spoil to the bund with the required lead and lift, etc.	,,	0 3 0	100		
3	Burnt stone jelly concrete in surki mortar ..	C.ft.	0 3 9	120		
4	Burnt brick in surki mortar	,,	0 4 0	20		
5	Burnt stone slabs 6" thick exposed surfaces one line dressed and fixed in surki mortar	S.ft.	0 4 6	20		
6	Plastering with surki mortar	Sqr.	3 8 0	8.00		
7	Rough stone work with the required lead, lift, jelly backing and jelly wedging, etc.	C.yd.	1 8 0	150		
8	Cutting holes in the slabs	Each	1 0 0	4		
9	Providing plug and rod with locking arrangement	L. S.	20 0 0	1		
	Waste weir.					
1	Approach clearing with the required lead and lift for the waste weir	C.yd.	0 1 0	10,426		
2	Burnt stone jelly concrete in surki mortar ..	C.ft.	0 3 9	265		
3	Burnt brick in surki mortar	,,	0 4 0	301		
4	Burnt stone slabs of 6" thick one line dressed and fixed in surki mortar	S.ft.	0 4 6	254		
5	Surki mortar plastering	Sqr.	3 8 0	303		
6	Rough stone apron including the required lead and lift with jelly packing and jelly wedging, etc.	C.yd.	1 8 0	58		

Notification dated 30th October 1938.

1. Sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M. on 24th November 1938, for restoring and improving Mylappanahalli Sorekaikunte Minor Tank, Register No.278 of Bangalore Taluk.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Bangalore Division, should be addressed to the Executive Engineer, Bangalore Division, in a sealed cover and superscribed as "Tender for restoring and improving Mylappanahalli Sorekaikunte Minor Tank of Bangalore Taluk." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a duplicate challan for having credited the deposit amount of Rs. 200 into the Treasury under "17 (a) Public Works Deposits" or Mysore Government Bonds, duly endorsed at face value or market value, whichever is less, as earnest money. The earnest money of the successful tenderer will be retained as security deposit for due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 25th November 1938. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental schedule contract form, after depositing an additional sum of Rs. 200 for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay specifications (1931).

6. Failure to comply with the condition 5 above, or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Bangalore, on all working days, between 11 A.M. and 5 P.M. and may be obtained from that officer on payment of Rs. 3 for each.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof, or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer, on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions, or additions at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of May 1939, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 200 per day, which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will however be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and bailing of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

Approximate quantities required for restoring and improving Mylappanahally Sorekaikunte Minor Tank, Reg. No. 278 of Bangalore Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
	Bund R. L. 55.50.		Rs. a. p.		
1	Cutting jungle and removing with roots ..	Grade	2 8 0	14	
2	Cutting steps and grips on bund and slopes ..	,,	3 0 0	10	
3	Earthwork to bund with the required lead, lift and consolidation	C.yd.	0 4 0	4,594	
4	Clearing the silt in the breached portion by buckets and basins	,,	0 3 0	100	
5	Turfing the rear slope and watering till it is satisfactory	S.yd.	0 0 9	3,631	
6	Gravel backing to revetment with required lead and lift	,,	0 8 0	307	
7	Old rough stone work with ⅓ new jelly packing and jelly wedging with required lead and lift ..	C.yd.	0 12 0	53	
8	New rough stone work with the required lead including jelly packing and jelly wedging, etc..	,,	1 12 0	740	
9	Puddle wall with clay mixed with good gravel in equal proportion including required lead and lift	,,	0 8 0	39	
10	Providing and fixing grade stones on bed slabs including cutting figures and painting, etc., complete	Each	2 4 0	14	
11	Providing and fixing index stones including painting, etc.	,,	0 6 0	14	
12	Providing and fixing Register No. stones on a bed slab including cutting figures and painting, etc.	,,	5 0 0	1	
13	Providing and fixing B. M. stones on bed slabs including cutting figures and painting, etc. ..	,,	5 0 0	2	
14	Providing and fixing gauge stones on a bed slab including masonry cutting figures and painting, etc.	,,	15 0 0	1	
	Sluice.				
1	Earthwork cut opening the bund and refilling the same with watering and tamping, etc. ..	C.yd.	0 5 0	100	
2	Earthwork excavating foundation and using the spoil to the bund with the required lead and lift, etc.	,,	0 3 0	50	
3	Burnt stone jelly concrete in surki mortar ..	C.ft.	0 4 0	60	
4	Burnt brick in surki mortar	,,	0 4 9	20	
5	Burnt stone slabs 6" thick exposed surfaces one line dressed and fixed in surki mortar ..	S.ft.	0 6 0	20	
6	Plastering with surki mortar	Sqr.	3 8 0	4·00	
7	Rough stone work with the required lead, lift, jelly backing and jelly wedging, etc.	C.yd.	1 12 0	100	
8	Cutting holes in the slabs	Each	1 0 0	4	
9	Providing plug and rod with locking arrangement (lock and key as per specification)	L. S.	20 0 0	1	
	Waste Weir 50 feet long at left end.				
1	Earthwork excavating foundation and using the spoil to the bund with the required lead and lift	C.yd.	0 3 0	43	
2	Burnt jelly concrete in surki mortar	C.ft.	0 4 0	71	
3	Burnt brick in surki mortar	,,	0 4 9	271	
4	Surki mortar plastering	Sqr.	3 8 0	3·82	
5	Burnt stone slabs 6" thick one line dressed and fixed in surki mortar	S.ft.	0 6 0	227	
6	Rough stone work with jelly packing and jelly wedging including required lead and lift ..	C.yd.	1 12 0	32	
7	Draft and approach clearing with the required lead and lift	,,	0 2 6	371	

No.	Items of work	Unit	Rate	Quantity	Cost
	Training Bank.		Rs. a. p.		
1	Earthwork for training bank by using the earth got by approach and draft clearing, etc. ..	C.yd.	0 1 0	496	
2	New rough stone work with jelly packing and jelly wedging including required lead and lift ..	,,	1 12 0	45	
3	Turfing the slopes and watering till it is satisfactory	S.yd.	0 0 9	355	

Notification dated 30th October 1938.

1. Sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M., on 22nd November 1938, for restoring Aralikatte Tank, Register No. 200 of Gargespura Village, Magadi Taluk.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Bangalore Division, should be addressed to the Executive Engineer, Bangalore Division, in a sealed cover and superscribed as "Tender for Aralikatte Tank Register No. 200 of Magadi Taluk." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a duplicate challan for having credited the deposit of Rs. 130 into the treasury under 17(a) Public Works Deposits, or Mysore Government Bonds, duly endorsed at face value or market value, whichever is less, as earnest money. The earnest money of the successful tenderer will be retained as security deposit for due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 23rd November 1938 at 3 P.M. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental schedule contract form, after depositing an additional sum of Rs. 130 for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay specifications (1931).

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Bangalore, on all working days between 11 A.M. and 5 P.M., and may be obtained from that officer on payment of Rs. 3 for each.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof, or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer, on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or

additions, at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of May 1939, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 130 per day which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind, not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will however be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer, in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations, wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D. so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work, and he must take precaution against all risk of accidents and, if necessary, provide for the same by insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

Approximate quantities required for restoring Aralikatte Tank, Reg. No. 200 of Gargeswarapura of Magadi Taluk.

No.	Items of work	Unit	Rate	Quantity	Rate to be quoted in	
					Words	Figures
			Rs. a. p.			
1	Clearing the jungle with roots	Grade	2 0 0	10		
2	Cutting grips and trenches	,,	2 0 0	10		
3	Earthwork to bund with the required lead, lift and consolidation	C.yd.	0 4 0	2,914		
4	Turfing the slopes of bund and watering till it is satisfactory	S.yd.	0 1 0	1,873		
5	Rough stone revetment now with the required lead, lift, jelly backing and jelly wedging, etc., complete	C.yd.	1 4 0	540		

No.	Items of work	Unit	Rate	Quantity	Rate to be quoted in	
					Words	Figures
			Rs. a. p.			
6	Gravel backing with required lead and lift ..	C.yd.	0 9 6	180		
7	Providing and fixing grade stones on bed slabs including cutting figures and painting, etc., complete	No.	2 6 0	10		
8	Providing and fixing index stones with painting, etc.	No.	0 6 0	10		
9	Providing and fixing B. M. stones on bed slabs including cutting figures and painting, etc., complete	No.	2 12 0	2		
10	Providing and fixing Register No. stone on a bed slab including cutting figures and painting	No.	2 12 0	1		
11	Consolidation charges for the earthwork available from the weir site	C.yd.	0 1 6	300		
	Constructing New Sluice.					
1	Earthwork cut opening the bund and refilling the same with watering and tamping, etc.	C.yd.	0 5 0	200		
2	Earthwork excavation for foundation and using the spoil to the bund with the required lead and lift	C.yd.	0 3 0	100		
3	Burnt stone jelly concrete in surki mortar ..	C.ft.	0 4 0	120		
4	Burnt brick in surki mortar	"	0 4 6	20		
5	Burnt stone slabs 6" thick exposed surfaces one line dressed and fixed in surki mortar	S.ft.	0 4 6	20		
6	Plastering with surki mortar	Sqr.	3 8 0	8·00		
7	Rough stone work with required lead, lift, jelly backing and jelly wedging, etc. ..	C.yd.	1 4 0	100		
8	Cutting holes in the slabs	Each	1 0 0	4		
9	Providing plug and rod with locking arrangement	L. S.	20 0 0	1		
	Waste Weir.					
			Rs. a. p.			
1	Earthwork draft clearing with required lead and lift	C.yd.	0 4 0	460		
2	Stone jelly concrete for foundation in surki mortar	C.ft.	0 4 0	75		
3	Burnt brick in surki mortar	C.ft.	0 4 6	236		
4	Plastering with surki mortar	Sqr.	3 8 0	2·89		
5	Burnt stone slabs 6" thick one line dressed and fixed in surki mortar	S.ft.	0 4 6	230		
6	Providing joggle joints	No.	0 8 0	8		
7	Rough stone apron new with required lead, lift, jelly backing, jelly wedging, etc., complete	C.yd.	1 4 0	31		

Notification dated 29th October 1938.

1. Sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, upto 2 P.M., on 25th November 1938, for restoring Volegeri Kallahalli Minor Tank of Anekal Taluk.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Bangalore Division, should be addressed to the Executive Engineer, Bangalore Division, in a sealed cover and superscribed as "Tender for restoring Volegeri Kallahalli Minor Tank, Anekal Taluk." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a duplicate challan for having credited into the treasury the deposit amount of Rs. 225 under 17 (*a*) P.W Deposits or Mysore Government Bonds, duly endorsed at face value or market value, whichever is less, as earnest money. The earnest money of the successful tenderer will be retained as security deposit for due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 26th November 1938 at 3 P.M. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender the successful tenderer will be required to execute an agreement in the Departmental Schedule after depositing an additional sum of Rs. 225 for the due fulfilment of the contract and for the execution of all items of work in accordance with the Bombay Specifications (1931).

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Bangalore Division, on all working days, between 11 A.M. and 5 P.M. and may be obtained from that officer on payment of Rs. 3 for each.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The work should be completed and handed over in a tidy condition to the Public Works Department by the end of August 1939, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 225 per day which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds to keep materials under cover and also for workmen.

(4) Arrange for protecting work during inclement weather.

(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.

(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.

(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.

(8) Provide arrangements for pumping and baling of water from excavations and foundations, wherever and whenever necessary with his own pumping apparatus, including necessary leading drains, slump pits, etc.

(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract and give such persons the use of ordinary scaffolding and ladders.

(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary, provide for the same by insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

Approximate quantities required for restoring Volagere Kallahalli Minor Tank of Anekal Taluk Register No. Nil.

No.	Items of work	Unit	Rate	Quantity	Rate to be quoted in	
					Words	Figures
	Bund at R.L. 56·00 *Top width* 4½.		Rs. a. p.			
1	Cutting grips and clearing jungle with roots	Grade	1 12 0	19		
2	Earthwork to bund with the required lead, lift and consolidation	C.yd.	0 3 3	10,333		
3	Turfing the slopes and watering till it is satisfactory	S.yd.	0 0 10	6,679		
4	New rough stone revetment with new jelly backing and jelly wedging including required lead and lift	C.yd.	1 10 0	815		
5	Old rough stone revetment with new jelly backing and jelly wedging including required lead and lift	,,	0 12 0	130		
6	Providing and fixing new grade stones on bed slabs including cutting figures and painting, etc.	Each	1 8 0	19		
7	Providing and fixing Index stones with painting, etc.	,,	0 6 0	19		
8	Providing and fixing Register No. stone on a bed slab including cutting figures and painting, etc.	Each	3 0 0	1		
9	Removing and refixing B. M. stones on bed slabs with cutting figures and painting, etc.	,,	1 0 0	2		
10	Providing and fixing new guage stone on a bed slab with necessary masonry work including cutting figures and painting, etc.	,,	10 0 0	1		
	Sluice at R.L. 43.70.					
1	Providing plug and rod as per specification with locking arrangement lock and key, etc.	,,	20 0 0	1		
	Weir Left at 52·00 *Natural.*					
1	Earthwork draft clearing	Chargeable to Bund.				
2	Approach clearing by blasting in hard rocky soil	C.yd.	2 0 0	76		
3	Earthwork for foundation	Chargeable to Bund.				
4	Burnt stone jelly concrete in surki mortar..	C.ft.	0 4 0	30		

No.	Items of work	Unit	Rate	Quantity	Rate to be quoted in	
					Words	Figures
5	Size stone in surki mortar	C.ft.	0 5 0	83		
6	New burnt stone slabs 6" thick all line dressed and fixed in surki mortar ..	S.ft.	0 6 0	15		
7	Cement pointing	Sqr.	3 0 0	1.00		
8	Providing rough stone apron with jelly packing and jelly wedging, etc., with the required lead	C.yd.	1 8 0	50		

Tender Notice dated 30th October 1938.

Sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M., on 23rd November 1938, for improving Doddabele Konankere Major Tank, Register No. 109 of Tyamagondalu Hobli, Nelamangala Taluk.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Bangalore Division, should be addressed to the Executive Engineer, Bangalore Division, in a sealed cover and superscribed as "Tender for improving Doddabele Konankere Register No. 109 of Nelamangala Taluk." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a duplicate challan for having credited the deposit amount of Rs. 125 into the treasury under 17 (a) Public Works Deposits or Mysore Government Bonds duly endorsed at face value or market value, whichever is less, as earnest money. The earnest money of the successful tenderer will be retained as security deposit for due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 24th November 1938 at 3 P.M. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice-Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental Schedule Contract Form after depositing an additional sum of Rs. 125 for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay Specifications (1931).

6. Failure to comply with the condition 5 above, or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Bangalore, on all working days between 11 A.M. and 5 P.M. and may be obtained from that officer on payment of Rs. 3 for each.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof, or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer, on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions, or additions at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of May 1939, failing which, the Executive Engineer may, at his discretion, levy a penalty of Rs. 125 per day, which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by Insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

Approximate quantities required for improving the Doddabele Konankere Major Tank, Register No. 109 of Thyamagondlu Hobli, Nelamangala Taluk.

Sl. No.	Items of work	Unit	Sanctioned		Rate quoted in	
			Quantity	Rates	Figures	Words
	1. Bund R.L. 58·00.			Rs. a. p.		
1	Clearing jungle	Grade	19	1 8 0		
2	Cutting grips	,,	19	2 4 0		
3	Earthwork to bund with the required lead, lift, including watering and tamping ..	C.yd.	6,050	0 3 6		

Sl. No.	Items of work	Unit	Sanctioned		Rate quoted	
			Quantity	Rates	Figures	Words
				Rs. a. p.		
4	Turfing and watering till it is satisfactory..	S.yd.	7,000	0 0 10		
5	Providing new grade stones with bed slabs cut and painted	No.	6	2 0 0		
6	Removing and refixing old grade stones including figuring, painting and bed slabs	„	15	0 8 0		
7	Figuring and painting Register No. stone..	„	1	0 8 0		
8	Do B. M. stones ..	„	2	0 8 0		
9	Do Gauge stone ..	„	1	5 0 0		
10	Rough stone revetment new with the required lead, lift, jelly backing and jelly wedging, etc.	C.yd.	60	2 0 0		
11	Removing and resetting old stone revetment	„	50	1 0 0		
	II. Waste Weir R.L. 52·00.					
1	Removing burnt stone coping slabs set in mortar	S.ft.	133	0 0 6		
2	Burnt brick in surki mortar	C.ft.	330	0 5 0		
3	Burnt stone jelly concrete in surki mortar	„	380	0 4 6		
4	Cement plastering to concrete apron ..	Sqr.	3·50	8 0 0		
5	Resetting old slabs in surki mortar ..	S.ft.	133	0 2 0		
6	Providing and fixing new burnt stone slabs one line dressed in surki mortar ..	„	20	0 6 0		
7	Plastering with surki mortar	Sqr.	4·00	3 8 0		
8	New rough stone revetment with the required lead, lift, jelly backing and jelly wedging, etc.	C.yd.	13	2 0 0		
9	Earthwork for raising wings of weir including consolidation	„	25	0 3 6		
10	Repairs to old revetment	L. S.	..	6 0 0		
	III. Sluices.					
1	Repairs to sluice (details to be given during execution)	L.S.	..	30 0 0		
	IV. Unforeseen items	„	..	100 0 0		

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

KOLAR DIVISION.

Abstract Notification dated 23rd October 1938.

The attention of the public is invited to the detailed notification dated 19th October 1938, published on pages 1911-1913, Part VI of the *Mysore Gazette*, dated 27th October 1938, calling for tenders for the "Restoration of Gujjanahalli Byrasandra Tank, Registered No. 360/164 of Duggasandra Hobli, Mulbagal Taluk."

The last date for receiving tenders is 21st November 1938 up to 12 Noon.

R. TIPPAIYA,
Executive Engineer.

TUMKUR DIVISION.

Abstract Notification dated 25th October 1938.

It is hereby notified for the information of the public that the last date, *viz.*, 25th October 1938, for receipt of tenders for the Restoration of Konankere Minor Tank, Gubbi Taluk, as notified in page 1824 of Part VI of the *Mysore Gazette*, dated 20th October 1938, has been extended to 10th November 1938.